



Schenectady County
Purchasing Department

620 State St- 2nd Floor
Schenectady, NY 12305
Purchasing@schenectadycounty.com
518.388.4240

ADDENDUM

RFB-2022-19
RENOVATIONS TO: SCHENECTADY COB LOBBY
C2 DESIGN GROUP

ADDENDUM #2

Issued Date: 06/22/2022

The purpose of this addendum is to provide detailed information to all Bidders. This addendum is hereby included in and made part of the Contract Documents, whether or not attached thereto. Receipt of this Addendum must be acknowledged on the bid form.

CONTENTS/RESPONSE TO QUESTIONS/REFERENCE TO ATTACHMENTS

Bid Opening New Date: June 30th, 2022, at 2:00 PM

- **01-15-00 Master Project Schedule: Revisions of project schedule dates.**

General Reference in Specifications: (*Change in Purchasing Department address:*)

*Purchasing Department County of Schenectady
Schenectady County Office Building
620 State Street - 2nd Floor
Schenectady, NY 12305
Phone: 518-388-4240*

General RFI's:

1. Alternate #4 – CRL Plaza Series Square Partition only accommodates 9/16” glass. Plans call for ½”, please advise?
 - a. Response: 9/16” clear tempered glass or manufactures specifications closest to ½” is acceptable.
2. Alternate #1 – Hardware set is calling for a Rim Cylinder and no locking mechanism, clarify that the vestibule won't utilize a locking system and would want a push/pull set, if not what is the locking hardware to match the Rim Cylinder?
 - a. Response: As per Alternate #1 hardware set, coordinate Rim Cylinder with County (locking) requirements.
3. Based on Drawing # AS101 the existing fireproofing is being removed. The fireproofing, spec. sec. 078100, indicates a reapplication to the abated floor above at a 2 hour



Schenectady County
Purchasing Department

620 State St- 2nd Floor
Schenectady, NY 12305
Purchasing@schenectadycounty.com
518.388.4240

ADDENDUM

unrestrained rating. In order to formulate a coherent bid the building structural drawings of this area would be needed for the existing steel sizes and to show what the floor above is comprised of. Please advise on the availability of these documents.

- a. The wall to the diner does not go all the way to the deck. There is a partial wall on the lobby side of the hard ceiling system and a beam on the diner side of the hard ceiling. Please see the attached two pictures that show above the ceiling.
- b. PSI will amend the variance to have the contractor remove the fireproofing up to the beam, including on the accessible side of the beam, and install a poly barrier from the ceiling to the beam along the wall.

Please acknowledge this addendum on your bid form.

END OF ADDENDUM #2